Owner: Engineering		SUBTL SR2-3xIT racks	SR2N03010NAA1
Author: Michael Gmerek	Vertiv Co.	10kW-No Redundancy	-SUBTL
Date: 4/1/2024		SmartRow 2 Submittal	Rev B

Contents

Contents1
SmartRow 2 Site Planning Guide
Interconnection Guide (ICG)
SmartRow 2 600mm IT Rack Outline
SmartRow 2 PMC Basic Outline
SmartRow 2 PMC Components
SmartRow 2 Row Cooling w Plenum Outline
SmartRow 2 PMU Detail
SmartRow 2 Cable Trough 300mm Outline
SmartRow 2 Cable Trough 600mm Outline
SmartRow 2 Assembly Scope of Work

		Smart Row 2 Site Planning Datasheet (208V, 3 phase, 4 wire + PE)											
[Configuration Number	Part Number	Max Row Capacity (kW)	IT Racks per Row	Capacity per Rack (kW)	Cooling Units per Row	pdu count	Main Input Breaker Size ⁶	Per Condenser Breaker Size	Per Condenser Dry Weight kg (lbs)	Row Dimensions (L x H x D) mm (in)7	Row Weight kg (lbs)	Min. Staging Area m2 (ft2)
	1	SR2N02010NAA1	10	2	5	1	2	100A	N/A ⁵	60 (132.3)	2100 (82.7) x 2271 (107) x 1400 (55.2)	1463 (3227)	14.41 (155.2)
	2	SR2N02010PAA1	10	2	5	1	4	100A	N/A ⁵	60 (132.3)	2100 (82.7) x 2271 (107) x 1400 (55.2)	1491 (3288)	14.99 (161.4)
	3	SR2N02010FAA1	10	2	5	2	4	100A	N/A ⁵	60 (132.3)	2400 (94.5) x 2271 (107) x 1400 (55.2)	2112 (4656)	17.67 (190.2)
lĪ	4	SR2N03010NAA1	10	3	3	1	3	100A	N/A ⁵	60 (132.3)	2700 (106.3) x 2271 (107) x 1400 (55.2)	1633 (3601)	15.76 (169.7)
ļ	5	SR2N03010PAA1	10	3	3	1	6	100A	N/A ⁵	60 (132.3)	2700 (106.3) x 2271 (107) x 1400 (55.2)	1675 (3694)	16.34 (175.9)
	6	SR2N03010FAA1	10	3	3	2	6	100A	N/A ⁵	60 (132.3)	3000 (118.2) x 2271 (107) x 1400 (55.2)	2296 (5061)	19.02 (204.8)
I	7	SR2N03020NAA1	20	3	6	1	3	175A	15A	118 (260.2)	2700 (106.3) x 2271 (107) x 1400 (55.2)	1863 (4108)	18.46 (198.8)
	8	SR2N03020PAA1	20	3	6	1	6	175A	15A	118 (260.2)	2700 (106.3) x 2271 (107) x 1400 (55.2)	1905 (4201)	20.51 (220.8)
	9	SR2N03020FAA1	20	3	6	2	6	175A	15A	118 (260.2)	3000 (118.2) x 2271 (107) x 1400 (55.2)	2526 (5568)	24.42 (262.9)
	10	SR2N04020NAA1	20	4	5	1	4	175A	15A	118 (260.2)	3300 (130) x 2271 (107) x 1400 (55.2)	2033 (4483)	19.81 (213.3)
	11	SR2N04020PAA1	20	4	5	1	8	175A	15A	118 (260.2)	3300 (130) x 2271 (107) x 1400 (55.2)	2089 (4607)	21.86 (235.3)
	12	SR2N04020FAA1	20	4	5	2	8	175A	15A	118 (260.2)	3600 (141.8) x 2271 (107) x 1400 (55.2)	2710 (5974)	25.77 (277.4)
	13	SR2N05020NAA1	20	5	4	1	5	175A	15A	118 (260.2)	3900 (153.6) x 2271 (107) x 1400 (55.2)	2203 (4858)	21.16 (227.8)
	14	SR2N05020PAA1	20	5	4	1	10	175A	15A	118 (260.2)	3900 (153.6) x 2271 (107) x 1400 (55.2)	2273 (5012)	23.21 (249.9)
	15	SR2N05020FAA1	20	5	4	2	10	175A	15A	118 (260.2)	4200 (165.4) x 2271 (107) x 1400 (55.2)	2894 (6380)	27.12 (292)
	 2. Floor sui 3. No buildi 4. Install in 5. 10kW co 6. Cable Si 	Environmental Co face must be lew ng sprinkler head accordance with ndenser power is zing: 100A = 3 A iensions do not ir	el and contin d should be w national and s sourced from WG ; 175A =	uous (expans vithin 19.7 in local electric m the indoor 2/0 AWG	sion joints seal (0.5 m). al codes unit	led, raised floo	or tile gaps	s sealed, no fl					
	IEET NO.	DRAWN BY:	0 202 THIS I ALL DISI) VERTIV GROUP CORPORAT IOCUMENT (AND THE INFOR INFORMATION CONTAINED) OSE OF SAME DIRECTLY O	ION CONFIDENTIAL AND PROPRI MATION IT CONTAINS) ARE THE IEREIN IN STRICTEST CONFIDE IN INDERCT V WITHOUT THE FO	ETARY, ALL RIGHTS RESERVED PROPERTY OF VERTIV GROUP VCE AND WILL NOT COPY, RET VERESS WITTEN PERMISSION	D.VERTIV AND THE VER CORPORATION BY AC RANSMIT, USE (EXCEP)	RTV LOGO ARE TRADEMARKS CCEPTING IT INTO YOUR POS T SOLELY FOR THE BENEFIT	OR REGISTERED TRADEMAR SESSION, YOU AGREE THAT ' JF VERTIV GROUP CORPOR', UMENT SHALL BE RETURNET	KS OF VERTIV GROUP CORPORATION YOU WILL KEEP THIS DOCUMENT AND ATION), SELL LEND, OR OTHERWISS TO VERTIV GROUP CORPORATION			
co). NQ.	DESIGNED BY:	TITLE			IMME	EDIATELY UPON REQUE	EST.			DATE (LATEST REV.)) VEI	RTIV


Vertiv Row Solution

PAGE DESCRIPTION:

1- Title page / cover sheet

Knowledge to Build Optimized Infrastructure Solutions





Vertiv[™] SmartRow[™] 2: 3x IT Rack 10kW

B 505 N. CLEVELAND AVE WESTERVILLE

OH 43081

Page	Page description
Row/1	Title page / cover sheet
/Row/2	Table of contents : =vRow/1 - =vRow+Thermal/13
Row/3	Structure identifier overview
Row/4	vRow Front View
vRow/4.a	vRow Top View
vRow/4.b	SR2 Components View
vRow/5	One Line PMC and UPS
vRow/5.a	One Line Diagram Thermal
vRow/6	Part List Vertiv Supplied
vRow/7	Part List Customer Supplied
vRow/8	Cable overview : =vRow+PMC-W201 - =vRow+Rack3-W213
=vRow/8.a	Cable overview : =vRow+Thermal-WB1 - =vRow+Rack2-W207
vRow+PMC/9	PMU Power Distribution
vRow+PMC/9.a	Power Distribution
vRow+PMC/9.b	GXT5 10k-A
=vRow+PMC/9.c	Emergency Fan Control
=vRow+PMC/9.d	RDU501
=vRow+PMC/9.g	PMC Logic
=vRow+PMC/9.h	POE Switch
=vRow+Rack1/10	IT Rack 1
=vRow+Rack2/11	IT Rack 2
vRow+Rack3/12	IT Rack 3
=vRow+Thermal/13	Thermal CRV1 & Condenser1

SHEET NO. 2 / 23	DRAWN BY: Nilesh Patil	© 2020 VERTU GRUP CORPORATION COMEIDENTIAL AND PROPRIETARY. ALL RIGHTS RESERVED VERTU NAID THE VERTU LOGA BETRADEMARKS OF VERTU GROUP CORPORATION THIS DOLIMENT (AND THE INFORMATION IT CONTAINS) ARE THE PROPERTY OF VERTU GROUP CORPORATION BY ACCEPTING IT INTO YOUR POSSESSION, YOU AGREE THAT YOU WILL KEEP THIS DOCUMENT AND ALL INFORMATION CONTRINEN HEREIN IN STRUCTEST COMPIDENCE AND WILL NOT COMP. RETRANSHIT LISE (SCEPT SOLEY FOR THE BENEFT) OF VERTU GROUP CORPORATION, SELL, LEINO, ON OTHERWISE			
CHANGE NO.	APPROVED BY: Jakub Fencl	IMMEDIATELY UPON REQUEST.	DATE (LATEST REV.	,	
PAGE DESCRIPTION: 2- Table of conte	ents : =vRow/1 - =vRow+Thermal/13	TITLE / DESCRIPTION: Vertiv [™] SmartRow [™] 2: 3x IT Rack 10kW	REVISION: B	505 N. CLEVELAND AVE WESTERVILLE OH 43081	

Structure identifier overview

Full designation	Structure description
Function designation	
=vRow	
+PMC	UPS, Network Switch, FC Controller, PMU
+Rack1	vRack 1
+Rack2	vRack 2
+Rack3	vRack 3
+Thermal	Thermal Components and Condenser


Please note:

This document is intended to provide guidance to a qualified electrical installer. The installer, owner, and end user are responsible for adhering to all applicable building and electrical codes, regulations, laws, and standards, and nothing in this document is intended to conflict therewith. Vertiv is not responsible for any failure to conform therewith. In addition, nothing in this document is intended to conflict with the applicable product manuals, installation guides, or other product documentation, which documents take precedence over this design document. You are responsible for adhering to guidance in the appropriate product documentation, but for your convenience, some such documents are accessible here:



Before installing, connecting to supply or start operation, please review the provided safety and regulatory statements. This system represents a functional unit of an IT infrastructure solution, and the installer, owner, and end user are responsible for its proper operation.







Vertiv[™] SmartRow[™] 2: 3x IT Rack 10kW


PAGE DESCRIPTION:	4- vRow Front View


B 505 N. CLEVELAND AVE WESTERVILLE

OH 43081









Link to CRD Vertiv Product Page

© 2020 VERTIV GROUP CORPORATION CONFIDENTIAL AND PROPRIETARY. ALL RIGHTS RESERVED. VERTIV AND THE VERTIV LOGO ARE TRADEMARKS OR REGISTERED TRADEMARKS OF VERTIV GROUP CORPORATION THIS DOCUMENT (MOT THE INFORMATION IT CONTINUES) ARE THE ROPERTY OF VERTIV GROUP CORPORATION BY ACCEPTING IT INTO YOUR POSSESSION, YOU AGREE THAT YOU WILL KEEP THIS DOCUMENT AND ALL INFORMATION CONTINUES HEREIN IN STRICTES CONFIDENCE AND WINAWARTILL OF CORP. RETIVE SOLLEY FOR THE BHEREIT OF VERTIV GROUP CORPORATION CORPORATION DISPOSE OF SAME, DIRECTLY OR INDIRECTLY, WITHOUT THE EXPRESS WRITTEN FEMILISTIC OF VERTIV GROUP CORPORATION, AND THIS DOCUMENT SHALL BE RETURNED TO VERTIV GROUP CORPORATION IMMEDIATELY UPON REQUEST. DRAWN BY: SHEET NO. 8 / 23 Nilesh Patil CHANGE NO. APPROVED BY: Jakub Fencl TITLE / DESCRIPTION: REVISION: 505 N. CLEVELAND PAGE DESCRIPTION: Vertiv[™] SmartRow[™] 2: 3x IT Rack 10kW 5.a- One Line Diagram Thermal AVE WESTERVILLE В OH 43081

		akub Fencl TIT	LE / DESCRIPTION: Vertiv™ SmartRow™ 2: 3x IT Rack 10kW	ATION DATE (LATEST REV.) REVISION: 505 N. CLEVELAND B AVE WESTERVILLE
9 / 23	DRAWN BY: N	lilesh Patil	OVERTIV GROUP CORPORATION CONFIDENTIAL AND PROPRIETARY ALL RIGHTS RESERVED URBITN AND THE VERTIV LOCO ARE TRADEMARKS OR REGISTREED TRADEMARKS OF VERTIV GROUP CORPO DOCUMENT (AND THE INFORMATION IT CONTAINS) ARE THE PROPERTY OF VERTIV GROUP CORPORATION BY ACCEPTING IT INIT YOUR POSSESSION, YOU AGREE THAT YOU WILL KEEP THES DOCUMENT INFORMATION CONTAINED FREEIN IN STRICTEST CONFIDENCE AND WILL DAT COOP, RETRANSATIVIS, EFCORET YOR THE ERREFT OF VERTIV GROUP CORPORATION, SOL CHERTIN GROUP CORPORATION, SOL CHERTIV GROUP CORPORATION, SOL CHERTING AND YOR TO YERTIV GROUP CORPORATION, AND THIS DOCUMENT SHALL BE RETURNED TO VERTIV GROUP CORPORATION, AND THIS DOCUMENT SHALL BE RETURNED TO VERTIV GROUP CORPORA	ent and Rwise
+Thermal-Condenser1 +Thermal/13.6:D		Thermal Outdoor Unit1	Air Cooled Condenser CCD10 for NAM CRD101 208 V 3ph	CCD100S-00A
+Thermal-CRD-1 +Thermal/13.0:A		Thermal Indoor Unit1	CRD101 10kW CRV row based Air cooling unit 300 mm wide 208 V 3Ph+PE	CRD101-0D00A
+Rack3-PDU3A +Rack3/12.2:B		PDU for Rack3	rPDU, Monitored Unit Level EC, 30A, 208V, 4.9kW, Vertical (36) IEC C13, (6) IEC C19, 15ft power cord with L6-30P, Black Powder Coat.	VP4N3025
+Rack2-PDU2A +Rack2/11.2:B		PDU for Rack2	rPDU, Monitored Unit Level EC, 30A, 208V, 4.9kW, Vertical (36) IEC C13, (6) IEC C19, 15ft power cord with L6-30P, Black Powder Coat.	VP4N3025
+Rack1-PDU1A +Rack1/10.2:B		PDU for Rack1	rPDU, Monitored Unit Level EC, 30A, 208V, 4.9kW, Vertical (36) IEC C13, (6) IEC C19, 15ft power cord with L6-30P, Black Powder Coat.	VP4N3025
+PMC-UPS-A-POD1 +PMC/9.b.5:A		POD PD2-103	Power Output Distribution 4x 5-15/20R T-Slot and 4x L6-30R	PD2-103
+PMC-UPS-A +PMC/9.b.2:A		GXT5 10 kW UPS-A	UPS GXT5 10 kW 208 V 60 Hz 2 Phases 6U, optinal 1x PD2 POD	GXT5-10KMVRT6UXLN
+PMC-RDU501 +PMC/9.d.0:A		RDU501 Controller	Liebert RDU501 Intelligent Infrastructure Management Solution	RDU501
+PMC-POE Switch +PMC/9.h.1:B		POE Switch	POE Switch for Smart Aisle or Smart Row NAM Solutions	POESwitch24Port
+PMC-PMU +PMC/9.0:A		10kw PMC	PMC,MSR2-New designed PMC for NAM (SKU TBD) - 1P = GXT5 - 20kVA Rack (600w, HMI, SmartLock x2, THD x1, LED, FC, 4G Modem), qty: 1, RDU 501 (8COM	I card x1) MSR2-NP2DS2G22
+PMC-EFC +PMC/9.c.0:A		Emergency Fan Control PDU	rPDU, Switched Unit Level Monitoring EC, 30A, 208V, 4.9kW, Horizontal	VP53100
Schematic / position		Device Function	Designation	SKU Number

evice Designation hematic / position	Designation	Description
Thermal-WA1 Thermal/13.4:D	Power cable between CRD to CCD 2 Wire + PE, 16AWG	Power Cable CRD to CCD
Thermal-WB1 Thermal/13.4:E	Fan speed control communication cable CRD to CCD	Fan speed control communication cable
/ 23 DRAWN BY:		RADEMARKS OF VERTU GROUP CORPORATION DWG NO. SR2A03010NAA1
	NIIESN Patil ALL INFORMATION CONTAINED HEREIN IN STRICTEST CONFIDENCE AND WILL NOT COPY, RETRANSMIT, ISE (EXCEPT SOLELY FOR THE BENEFIT OF VERTIV GROUP DISPOSE OF SAME, DIRECTLY OR INDIRECTLY, WITHOUT THE EXPRESS WRITTEN PERMISSION OF VERTU GROUP ONE ORDERATION, AND THIS DOCUMENT SHALL BE F IMMEDIATELY UNOR REQUEST.	CORPORATION), SELL, LEND, OR OTHERWISE

5

9

0

2

2

Cable overview

2

3

0

А

в

с

D

Е

Cable type	Function text	Device tag	Conductors	Cross-section (AWG)	Length (m
Smart door lock cascade	PMC to RACK1 power cascade cable	+PMC-W201	2	22	0.85
	RACK1 to RACK2 power cascade cable	+Rack1-W201	2	22	0.85
	RACK2 to RACK3 power cascade cable	+Rack2-W201	2	22	0.85
	RACK3 to CRD1 power cascade cable	+Rack3-W202	2	22	0.85
Communication cable	PMU to 4DI SPD communication network cable	+PMC-PMU-W104	1		1.7
	PMU to RDU501 COM3 meter communication network cable	+PMC-PMU-W105	1		1.8
	PMU to RDU501 D02 Control Red Light Cable	+PMC-PMU_LED Control-W102	1		1.8
	PMU to RDU501 DO1 Strobe siren control cable	+PMC-PMU_LED Control-W103	1		
	PMC to RDU501_COM1 intelligent door lock front door com. cable	+PMC-W101	1		0.9
	4DI to RDU501 Sensor2 SPD Communication Network Cable	+PMC-W106	1		0.3
	PMC to RDU501_ COM1 intelligent door lock rear door com. cable	+PMC-W107	1		0.9
	RDU501 COM2 to HMI communication cable	+PMC-W108	1		0.8
	PMC to RDU501 to PMC cabinet THD communication cable	+PMC-W109	1		0.7
	FC to Switch communication cable		0.8		
	PDU to Switch communication cable	+Rack1-W115	1		3.5
	PDU1A to PDU2A communication cable	+Rack2-W116	1		3
	PDU2A to PDU3A communication cable	+Rack3-W116	1		3
	CRD1 to Switch communication cable	+Thermal-W110	1		3.5
	Smoke1 to CRV-Door microswitch cable	+Thermal-W401	1		3.5
Emergency fan to FC	PMC Emergency fan to FC controller cable	+PMC-W209	3	18	1.2
	Rack1 Emergency fan to FC controller cable	+Rack1-W208	3	18	4.5
	Rack2 Emergency fan to FC controller cable	+Rack2-W208	3	18	4.5
	Rack3 Emergency fan to FC controller cable	+Rack3-W208	3	18	5.5
Front door light cascade	PMC to Rack1 front door LED light power cable	+PMC-PMU_LED Control-W210	4	20	1
	RACK1 to RACK2 front door LED light cascade cable	+Rack1-W210	4	20	0.75
	Cascaded cable for the end RACK front door light	+Rack2-W211	4	20	0.75
Front door microswitch cascade	PMC to RACK1 front door microswitch cascade cable	+PMC-PMU_LED Control-W212	2	20	0.75

4

5

6

8

9

Please note: Always when "conductor" = 1, or "Cross-section" is empty, it represents a network/communication cable.

HEET NO. 11 / 23	DRAWN BY: Nilesh Patil	© 2020 VERTIV GROUP CORPORATION CONFIDENTIAL AND PROPRIETARY, ALL RIGHTS RESERVED.VERTIV AND THE VERTIV LOGO ARE TRADEMARKS OR REGISTERED TRADEMARKS OF VERTIV GROUP CORPORATION THIS DOLMENT (AND THE INFORMATION IT CONTAINES) ARE THE PROPERTY OF VERTIV GROUP CORPORATION BY ACCEPTING IT TIND YOUR POSSESSION, YOU AGREE THAT YOU WILL KEEP THIS DOLMENT AND ALL INFORMATION CONTAINED HERIN IS TRATCISTIC CONFIDENCE AND WILL NOT COMP. RETAINSHIT, JSE (2004F) SOLELY FOR THE BRONE ORDER/OLD CORPORATION BY ACCEPTING IT TIND YOUR DOLMARIES AND THE AND THE AND THE TRADEMARKS OF REGISTERED TRADEMARKS OF VERTIVATION OF THE AND THE			
HANGE NO.	APPROVED BY: Jakub Fencl	IMMEDIATELY UPON REQUEST.	DATE (LATEST REV.)	SLIN
		TITLE / DESCRIPTION:	REVISION:	505 N. CLEVELAND	
	w : =vRow+PMC-W201 - -PMU_LED_Control-W212	Vertiv [™] SmartRow [™] 2: 3x IT Rack 10kW	B	AVE WESTERVILLE OH 43081	

Cable overview

2

0

Α

в

С

D

Е

Cable type	Function text	Device tag	Conductors	Cross-section (AWG)	Length (m
Front door microswitch cascade	RACK1 to RACK2 front door microswitch cascade cable	+Rack2-W212	2	20	0.75
	Cascade cable for the end RACK front door microswitch	+Rack3-W213	2	20	0.75
Interconnection CRV/Condenser	Fan speed control	+Thermal-WB1	2	22	
Power Cable	CRD to condensor power cable	+Thermal-WA1	3	16	
Power cable	PMU to PMC rear door LED light power cable	+PMC-PMU_LED Control-W07	2	20	1.2
	PMU to PMC front door LED light power cable	+PMC-PMU_LED Control-W09	4	20	1.75
	PMU to PMC front door microswitch power cable	+PMC-PMU_LED Control-W11	2	20	1.25
	PMU to PMC rear door microswitch power cable	+PMC-PMU_LED Control-W12	2	20	1.25
	PMU to UPS-A input cable	+PMC-W01	4	6	2.4
	UPS-A to PMU output cable	+PMC-W03	3	20	0.8
	PMU to CRD1 output cable	+PMC-W05	4	12	1.5
	PMU to PMC intelligent door lock power cable	+PMC-W06	2	22	0.85
	PMU to HMI power cable	+PMC-W08	2	22	2.2
Rear door light cascade	PMC to Rack1 rear door LED light power cable		1		
	RACK1 to RACK2 rear door LED light power cable	+Rack1-W216	2	20	0.75
	Cascading cable for rear door light of the end RACK	+Rack2-W217	2	20	0.75
Rear door microswitch cascade	PMC to RACK1 rear door microswitch cascade cable	+PMC-PMU_LED Control-W214	2	20	0.75
	RACK1 to RACK2 rear door microswitch cascade cable	+Rack2-W214	2	20	0.75
	Cascade cable for rear door microswitch of end RACK	+Rack2-W215	2	20	0.75
	=	+Rack3-W215	2	20	0.75
Smart door lock cascade	RACK1 to RACK2 communication cascade cables	+Rack1-W205	1		0.85
	RACK2 to RACK3 communication cascade cables	+Rack2-W205	1		0.85
	RACK3 to CRD1 communication cascade cables	+Rack3-W206	1		0.85
THD cascading	PMC to RACK1 Cascade Cable	+PMC-W207	1		2
	RACK1 to RACK2 Cascade Cable	+Rack1-W207	1		
	RACK2 to RACK3 Cascade Cable	+Rack2-W207	1		

4


5


6


9


Please note: Always when "conductor" = 1, or "Cross-section" is empty, it represents a network/communication cable.


© 2020 VERTIV GROUP CORPORATION CONFIDENTIAL AND PROPRIETARY. ALL RIGHTS RESERVED. VERTIV AND THE VERTIV LOGO ARE TRADEMARKS OR REGISTERED TRADEMARKS OF VERTIV GROUP CORPORATION THIS DOCUMENT (AND THE INFORMATION IT CONTAINES) ARE THE PROPERTY OF VERTIV GROUP CORPORATION BY ACCEPTING IT INTO YOUR POSSESSION, YOU AGREE THAT YOU WILL KEEP THIS DOCUMENT AND ALL INFORMATION ATTICONTAINES HERE IN STRUCTES TO ORIBIDNE AND WILL NOT COMP, RETAINED YOLK YOU THE BENEFY SOLELY FOR THE BENEFY DISPOSE OF SAME, DIRECTLY OR INDIRECTLY, WITHOUT THE EXPRESS WRITTEN FEMILISATION OF VERTIV GROUP CORPORATION, AND THIS DOCUMENT SHALL BE RETURNED TO VERTIV GROUP CORPORATION IMMEDIATELY UPON REQUEST. DRAWN BY: SHEET NO. 12 / 23 Nilesh Patil VERTIV. APPROVED BY: CHANGE NO. Jakub Fencl TITLE / DESCRIPTION: REVISION: 505 N. CLEVELAND PAGE DESCRIPTION: Vertiv[™] SmartRow[™] 2: 3x IT Rack 10kW 8.a- Cable overview : =vRow+Rack2-W212 -AVE WESTERVILLE В OH 43081 =vRow+Rack2-W207



















	0	1	2	3	4	5	6	7		8	9
А		+PMC					9.c.8:	.c			
в			=vRow+PMC-POE Switc POESwitch24Port POE Switch	ch			-POE Su -PS1-X1	2 PE			
с			Port 1 Port 2 Port 3 Port 1 Port 2 Port 3 Port 2 Port 3 Port 3 Port 2 Port 3 Port 3 Port 3 Port 3	Pot 4 Pot 5 Pot 6 Pot 7 Fot 4 Pot 5 Pot 7 Fot 7 F	Port 8		-X1 Mains Input C14	2 PE			
D			-RDU501_LAN2 -Rad&1/0.78 +Network_PDU1A -Network_EFC	9.b.1.E Network_UPS-A +Thermal/13.3.A +Thermal/13.3.A							
E	ET NQ.	DRAWN BY:		© 2020 VERTIV GROUP CORPORATION CONFIDENTIAL AN	D PROPRIETARY, ALL RIGHTS RESERVED VERTTV A	ID THE VERTIV LOGO ARE TRADEMARKS OR REGIST	ERED TRADEMARKS OF VERTIV GROUP CORPORATI		0201001444		
	19 / 23		Nilesh Patil	© 2020 VERTIV GROUP CORPORATION CONFIDENTIAL AN THIS DOCUMENT (AND THE INFORMATION IT CONTAINS) ALL INFORMATION CONTAINED HEREIN IN STRICTEST (DISPOSE OF SAME, DIRECTLY OR INDIRECTLY, WITHOU	ARE THE PROPERTY OF VERTIV GROUP CORPORAT CONFIDENCE AND WILL NOT COPY, RETRANSMIT, U IT THE EXPRESS WRITTEN PERMISSION OF VERTIV	ION BY ACCEPTING IT INTO YOUR POSSESSION, YO SE (EXCEPT SOLELY FOR THE BENEFIT OF VERTIV GI GROUP CORPORATION, AND THIS DOCUMENT SHAL	J AGREE THAT YOU WILL KEEP THIS DOCUMENT AN ROUP CORPORATION), SELL, LEND, OR OTHERWISE L BE RETURNED TO VERTIV GROUP CORPORATION	DATE (LATEST REV.	AU3010NAA1		
	NGE NO.	APPROVED BY	Jakub Fencl	TITLE / DESCRIPTION:	IMMEDIALELT OF	UN REQUEST.		REVISION:	505 N. CLEVELAN		VERTIV
PAG	E DESCRIPTION: 9.h- POE	E Switch		Vertiv™	SmartRow™ 2: 3x IT Rac	k 10kW		B	AVE WESTERVILL OH 43081		



































SCOPE OF WORK

SmartRow2 Assembly

SERVICE SUMMARY

Feature	Detail
On-Site Service	Site trip(s) within the 48 contiguous states. Visit(s) to be scheduled by the customer between 7 am-5 pm, Monday-Friday (excluding weekends & national holidays).
Customer Support	Includes access to the Customer Resolution Center (1-800-543-2378) and the Vertiv Customer Services Network Online Internet portal for extent of product warranty.
Consolidation	The SmartRow2 includes numerous shippable units (typically pallets or boxes) that originate from multiple factories and suppliers. Vertiv consolidates these items into a single customer shipment and reduces the likelihood of shippable units being lost at the customer site. This benefits the customer by relieving the burden of keeping track of multiple partial shipments.
Inside Delivery	Vertiv Service will move the shippable units from the delivery truck to the Staging Area. Vertiv Services will unpackage the shippable units and remove/dispose of the packaging material so that it is ready for assembly. Vertiv will verify that all material on the sales order has been received.
Project Management	Included with Consolidation and Inside Delivery. Vertiv will assign a project manager for the project. The Project Manager will supervise the Consolidation and Inside Delivery Process and communicate hardware shipment schedules with the customer.
Assembly	SmartRow2 is assembled onsite by Vertiv factory-trained and authorized technicians equipped with Vertiv Proprietary tools and software. Vertiv CEs and Vertiv Partners are the only approved OEM service providers for Vertiv products. These technicians are supervised by a Site Manager who also gathers site- specific requirements like safety and work procedures
Factory Startup	Warranty inspection and startup validates the warranty and initializes the warranty coverage period

SERVICE PERFORMED

Consolidated Shipment

Shippable units may be available at time of order or built-to-order with a lead time. Vertiv safely stores these items in-warehouse until the customer is ready to receive the SmartRow2 in a single shipment

Inside Delivery

Vertiv Services will deliver the shippable units from the delivery truck to the Staging Area. Vertiv Services will unpackage the shippable units and remove/dispose of the packaging material so that it is ready for assembly. Vertiv will verify that all material has been received.

Change order option:

• There must be an appropriate loading dock with continuous, level floor from the dock to the staging area. If the shippable units must be moved up/down stairs, the customer must provide a suitable elevator, or charges for special rigging will be incurred. If the customer does not have an appropriate loading dock, nominal charges may/may-not apply for a lift-truck delivery.

Scope of Work | Vertiv Commissioning

VERTIV.

Avocent[®] Chloride[®] Liebert[®] NetSure[™] Trellis[™]

Page 3 of 3

Rev: 08/30/2022

© 2022 Vertiv Group Corp. All rights reserved. Vertiv™ and the Vertiv logo are trademarks or registered trademarks of Vertiv Group Corp. All other names and logos referred to are trade names, trademarks or registered trademarks of their respective owners. While every precaution has been taken to ensure accuracy and completeness here, Vertiv Group Corp. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications, rebates and other promotional offers are subject to change at Vertiv's sole discretion upon notice.

Project Management

Vertiv will assign a project manager and a site manager for the project.

The Project Manager will supervise the Consolidation and Inside Delivery Process and communicate schedules with the customer.

The Site Manager will supervise the assembly, startup, warranty inspection and turn over the SmartRow2 to the customer

Site-Specific Requirements

All personnel will be available for up to two hours per week for Site Access, Safety Training and other site-specific requirements Change Order Option:

Vertiv can quote a price for additional man-hours if 2 hours per week is insufficient

Assembly

•

There shall be continuous, level floor between the Staging Area and the Installation Location so that heavy items can be moved via casters/pallet jacks.

Change Order Option:

• If there is not continuous level floor, the customer must provide or pay for any necessary lift/rigging equipment.

Vertiv PMC, including RDU501 SmartRow2 Controller/Display

Vertiv will position, level, and bay together the PMC as described in the submittal documents.

The customer is responsible for providing primary electrical power to the PMC.

Vertiv will program and configure the SmartRow2 RDU501 controller/display. This includes setting IP addresses so that the customer can monitor the system status remotely

Change Order Option:

 Vertiv will quote IP addressing of equipment on the customer network, but this would be done by other personnel and scheduled separately. This is outside the scope of SmartRow2 assembly.

Vertiv IT Rack(s)

Vertiv will position, level, and bay together the Vertiv IT Racks as described in the submittal documents.

Vertiv will not populate racks with customer IT gear, including blanking panels, servers, shelves, etc.

The customer must define addressing conventions (1,2,3,4, right-to-left or left-to-right) prior to start of work.

Cable Trays

Vertiv will install the SmartRow2 cable trays that are included with the SmartRow2 solution as described in the submittal documents

Liebert® CRV's, Temperature Sensors, Modbus cables, and associated Plenums

Vertiv will position and level the Liebert® CRV and attach the associated plenums to provide cooling to the SmartRow2.

Vertiv will connect the necessary temperature sensors.

The customer is responsible for piping and primary power to the CRV along with connecting CANBus cable between the CRV and heat rejection. All specific requirements (such as piping traps and proper electrical grounding) for correct product installation are detailed in the product installation manual.

After the SmartRow2 is assembled and the Liebert[®] CRV is piped and powered by the customer in accordance with the product installation manual, Vertiv will perform a factory warranty inspection along with the rest of the SmartRow2

Liebert[®] MC / CCD Condensers for Liebert[®] CRV's

VERTIV.

Scope of Work | Vertiv Commissioning

Avocent[®] Chloride[®] Liebert[®] NetSure[™] Trellis[™]

Page 3 of 3

Rev: 08/30/2022

© 2022 Vertiv Group Corp. All rights reserved. Vertiv[™] and the Vertiv logo are trademarks or registered trademarks of Vertiv Group Corp. All other names and logos referred to are trade names, trademarks or registered trademarks of their respective owners. While every precaution has been taken to ensure accuracy and completeness here, Vertiv Group Corp. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications, rebates and other promotional offers are subject to change at Vertiv's sole discretion upon notice.

Project Management

The customer is responsible for installing the associated heat rejection. This includes primary power, CANBus communication wire, piping, refrigerant charging, and all other tasks in the Installation Manual. Any/all penetration points in the walls/ceilings/floors for any wiring or piping are also the customer's responsibility.

Rack PDUs

Vertiv will install and connect all rack PDUs (if applicable) including GXT5 power extensions (if applicable) as described in the submittal documents

Liebert[®] GXT5 Single Phase UPS's

Vertiv will install and connect all Liebert[®] GXT5 UPS's and connect power within the PMC cabinet and output to the PDUs as described in the submittal documents.

Additionally, Vertiv will install ancillary equipment such as Maintenance bypass and PD2-103 cabling and connectors if not already preinstalled.

After the SmartRow2 is assembled and Primary Power to the SmartRow2 is provided by the customer, Vertiv will perform factory startup of all GXT5 equipment along with the rest of the SmartRow2

Switch

Vertiv will install and connect the switch within the PMC cabinet. as described in the submittal documents

Firmware Updates

Vertiv will update firmware of any/all units to the current revision level. Shippable units are sourced globally and firmware evolves as products may be in stock with prior revisions

Wiring

Vertiv will run all necessary wiring for power and communication between cabinets as part of assembly. This includes setting IP/DIP switch settings for proper communication between the device and the PMC

Accessories

The SmartRow2 is available with lights, door locks/sensors, temperature sensors that Vertiv will connect and install.

Services associated with cameras are sold separately and out-of-scope for the SmartRow2 Assembly

RDU Monitor SmartRow2 mobile application

Services associated with the RDU Monitor SmartRow2 mobile applications are quoted separately and out-of-scope for SmartRow2 assembly

ASSUMPTIONS AND CLARIFICATIONS

• Vertiv start-up validates product warranty.

Scope of Work | Vertiv Commissioning

- Defects or damage resulting from installation not performed by Vertiv are not covered.
- Parts and Labor coverage is in accordance with Product Warranty. If a modified warranty is purchased, terms default to that specific package.
- Any customer site visit is limited to eight (8) hours per visit. Any time beyond forty (40) hours/wk or eight (8) hrs/day or additional Startup visits will be billed separately.

0	VERTIV.	
---	---------	--

Avocent* Chlori	de* Liebert*	NetSure™	Trellis™	Rev: 08/30/2022	Page 3 of 3

© 2022 Vertiv Group Corp. All rights reserved. Vertiv[™] and the Vertiv logo are trademarks or registered trademarks of Vertiv Group Corp. All other names and logos referred to are trade names, trademarks or registered trademarks of their respective owners. While every precaution has been taken to ensure accuracy and completeness here, Vertiv Group Corp. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications, rebates and other promotional offers are subject to change at Vertiv's sole discretion upon notice.



- Expenses incurred due to delays that are beyond the control of Vertiv may be billed at cost.
- Startup visit must be scheduled confirmation of proper installation (if Vertiv not involved with installation).
- This pricing excludes any load bank testing. This can also be quoted separately if required.
- Pricing excludes activities associated with 3rd party commissioning
- Pricing excludes any type of circuit breaker NEMA testing. This can also be quoted separately if required.
- Customer/Installing contractor is responsible for providing elevated access as necessary.
- Any additional requests beyond the scope of this document will be billed separately by Vertiv.
- Vertiv will not perform physical changes to the site building (such as drilling holes, etc.)

CUSTOMER RESPONSIBILITIES

In order to provide timely, accurate and thorough execution of the services described herein, Vertiv requests the following:

- Point of Contact: Provide an authorized point of contact(s), specific for the scope of work, for scheduling and coordination purposes.
- Scheduling: Make dates available for scheduling service. All visits must be requested 4 weeks in advance for assembly and 10 days for startup/warranty-inspection of need by contacting the Vertiv Project Manager. Site must be available for 5 consecutive business days. Customer may choose to pay for premium time if weekend work is necessary.
- Site Access: Prior to time of scheduled work, provide site access including any customer required escort, security clearance, safety training and badging for Vertiv personnel.
- Equipment Access: Convenient access to the equipment covered by the Scope of Work. Prior to scheduled time of work, notify Vertiv personnel of any special requirements for equipment access including lifts, ladders, etc.
- Shutdown: Service may require shutdown of load to ensure electrical connection integrity.
- Notification: If for any reason the work cannot be performed during scheduled time, notify Vertiv personnel 24-hours prior to scheduled event.
- Provide Method of Procedure (MOP) requirements/ templates, and required review period(s)

TERMS AND CONDITIONS

Subject to all Terms & Conditions as noted in the Vertiv Terms & Conditions or the terms of a Master Agreement between the parties, if any, shall apply.

Scope of Work | Vertiv Commissioning

VERTIV.

Avocent[®] Chloride[®] Liebert[®] NetSure[™] Trellis[™]

Rev: 08/30/2022

Page 3 of 3

© 2022 Vertiv Group Corp. All rights reserved. Vertiv[™] and the Vertiv logo are trademarks or registered trademarks of Vertiv Group Corp. All other names and logos referred to are trade names, trademarks or registered trademarks of their respective owners. While every precaution has been taken to ensure accuracy and completeness here, Vertiv Group Corp. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications, rebates and other promotional offers are subject to change at Vertiv's sole discretion upon notice.